



## ST. TAMMANY PARISH

PATRICIA P. BRISTER  
PARISH PRESIDENT

**July 9, 2018**

Please find the following addendum to the below mentioned BID.

**Addendum No.:** 1

**Bid#:** 314-00-18-23-2

**Project Name:** 2018 District 12 & 14 Panel Replacements

**Bid Due Date:** Thursday, July 12, 2018

### QUESTIONS & ANSWERS:

---

**Question 1:** Bid package, pages 47 – 51: Has hand written descriptions for each site in a notebook. I can read everything on the left side of the notebook but nothing on the right side of the notebook. Is there supposed to be info on the Right side of the notebook?

**Answer 1:** The right side was left blank intentionally except for the one on Oak Harbor.

**Question 2:** Bid package, pages 47 - 52. For each site it gives an average panel size. Can you clarify which measurement is the longitudinal measurement and which is the Transverse measurement?

**Answer 2:** Typically the longest measurement is the longitudinal side.

**Question 3:** Bid package, pages 12 - 46. In the description of "Remove/Replace/Repair Concrete Panels and Concrete Rollover Curb" for each site it states "Base repair and/or patch is not limited to a square yardage quantity, **but may include the entire panel if directed by Department of Public Works inspection staff.** This item is at no direct pay." If inspection staff does not direct the contractor to remove and replace the entire base (because the base replacement is a lumped in with Remove / Replace Concrete Panels and Concrete Rollover Curb price) it is possible that the government will be billed for it anyway. For bidding purposes, Can the government include on the bid form a unit line item for remove, replace and fill base material?

**Answer 3:** No, the Parish cannot add a pay item because it is estimated as such. The pay item states that after removing the concrete panel the Contractor is to remove the base material 8" thick below the bottom grade of the new 8" concrete panel. If the ground below that 8" base material is still unsuitable the Contractor is to remove that section of bad sub-base at no direct pay. Typically after removing the 8" of material the sub-base is still sufficient to install the new river or pumped sand base and compact. The Parish Inspector or Construction Manager will inspect the base before the Contractor pours concrete to ensure the base is acceptable.

**Question 4:** Can the government provide a rough sketch of the panels to be replace?

**Answer 4:** No, the panels have not been picked out yet, but this bid item is by the square yard.

### End of Addendum #1

PROCUREMENT DEPARTMENT

P.O. BOX 628 | COVINGTON, LOUISIANA | 70434 | PROCUREMENT@STPGOV.ORG | 985-898-2520

WWW.STPGOV.ORG