



ST. TAMMANY PARISH

MICHAEL B. COOPER
PARISH PRESIDENT

July 20, 2021

Please find the following addendum to the below mentioned QUOTE.

Addendum No.: 1

Quote#: 21-42-1

Project Name: Brown Dr Drainage Repair

Quote Due Date: July 28, 2021

GENERAL INFORMATION:

1. Please add the Project Specifications to Attachment A. (Attached)

ATTACHMENTS:

1. Attachment A Specifications.pdf

End of Addendum # 1

Located on the east side of the Cul de Sac at the end of Brown Rd. in Slidell.

Item	Description	Length	Width	Quantity	Unit
	<p>General Notes:</p> <ol style="list-style-type: none"> 1. Contractor shall field verify all quantities and measurements. 2. Contractor shall be responsible for locating and protecting all existing utilities. 3. Two-way traffic shall be maintained at all times during construction. 4. Prior to beginning work, contractor will provide temporary signs and barricades at no direct pay: furnish, install, maintain and remove temporary signs, construction signs and / or barricades; and provide flagmen to comply with all other requirements regarding the projection of the work, workers and safety of the public. Work shall be done in accordance with LA DOTD Standard Specifications for Roads and Bridges, Sec. 713. 5. Driveway aprons shall be tied-in to existing hard surfaced drives or extend two (2) feet behind the culvert, whichever is greater. For clarification purposes, tie-in new asphalt to existing asphalt/concrete aprons at no direct pay. 6. All turning radii shall be a minimum of thirty-five (35) feet. 7. All existing sewer lines shall be tied-in at no direct pay. 8. For clarification purposes, tie-in new asphalt to existing asphalt aprons at no direct pay on existing gravel roads. 9. Any <i>additional work</i> performed by the contractor <i>without prior written approval</i> from the St Tammany Parish Department of Public Works, the cost of the work will be borne by the contractor and will not be reimbursed by the Parish. 				
	<p>Project Summary: Supply and install catch basins, culverts and embankment.</p>				
1	<p>Mobilization: All labor and materials necessary to accomplish preparatory work and operations, including those necessary for movement of personnel, equipment, supplies and incidentals to the project site. Mobilization costs shall follow rules called out in the LA DOTD Standard Specifications for Roads and Bridges, Sec. 727.</p>			1	Lump Sum

Located on the east side of the Cul de Sac at the end of Brown Rd. in Slidell.

Item	Description	Length	Width	Quantity	Unit
2	Traffic Rated Catch Basin with Cast Iron Drop Inlet Grate: All labor and materials to provide or build (2) 4' x 4' Traffic Rated Conflict Box with 24" x 24" cast iron grate. The lid of catch basin shall be 8" thick and the TOC shall be 2/10 th 's lower than the adjoining grade. All work shall be done in accordance with LA DOTD Standard Specifications for Roads and Bridge Sec. 702, 2016 Edition. All debris shall be removed at no direct pay.			2	Each
3	18" HDPE Culvert: All labor and materials necessary to provide and install 18" HDPE culverts. Work shall include material necessary to install per the manufacturer's recommendation. All work shall be done in accordance with LA DOTD Standard Specifications for Roads and Bridges, Sec. 701, 2016 Edition. All debris is to be removed at no direct pay.			52	Linear Foot
4	Embankment: All labor and materials necessary to provide and install embankment over pipe. Work shall include all compaction and grading required. The contractor shall grade the materials so that there is positive drainage into the catch basins. All work shall be done in accordance with the LA DOTD Standard Specifications for Roads and Bridges, Sec. 203, 2016 Edition. All debris shall be removed at no direct pay.			21	Cubic Yard