



ST. TAMMANY PARISH

PATRICIA P. BRISTER
PARISH PRESIDENT

April 17, 2018

Please find the following addendum to the below mentioned QUOTE.

Addendum No.: 1

Quote#: 310-00-18-08-1

Project Name: Greenleaves Blvd

Quote Due Date: Wednesday, April 25, 2018

GENERAL INFORMATION:

- 1. Please add the Unit Price Sheet to “Attachment A”.**
- 2. Please add the Project Specifications to “Attachment A”.**

ATTACHMENTS:

- 1. Unit Price Sheet.pdf**
- 2. Project Specifications.pdf**

<< End of Addendum #1 >>

QUOTE UNIT PRICE FORM

TO: St. Tammany Parish Government QUOTE FOR: Greenleaves Blvd
21454 Koop Drive, Suite 2F Bid No.: 310-00-18-08-1
Mandeville, LA. 70471
(OWNER TO PROVIDE NAME AND ADDRESS OF OWNER)
(OWNER TO PROVIDE PROJECT NAME & OTHER IDENTIFYING INFO)

UNIT PRICES: This form shall be used for any & all work required by the Quote Documents & described as unit prices. Amounts shall be stated in figures & only in figures.

REF NO.:	Description:	Mobilization		UNIT PRICE EXTENSION (Quantity times unit price)
		<input checked="" type="checkbox"/> BASE QUOTE	<input type="checkbox"/> ALT #	
727-01		QUANTITY	UNIT OF MEASURE	UNIT PRICE
		1	LS	
713-01	Temporary Signs and Barricades	<input checked="" type="checkbox"/> BASE QUOTE	<input type="checkbox"/> ALT #	UNIT PRICE EXTENSION (Quantity times unit price)
		QUANTITY	UNIT OF MEASURE	UNIT PRICE
		1	LS	
706-03-00500	Remove/Replace/Repair Concrete Panels and Concrete Rollover Curbs	<input checked="" type="checkbox"/> BASE QUOTE	<input type="checkbox"/> ALT #	UNIT PRICE EXTENSION (Quantity times unit price)
		QUANTITY	UNIT OF MEASURE	UNIT PRICE
		775	SY	
	Description:	<input type="checkbox"/> BASE QUOTE	<input type="checkbox"/> ALT #	UNIT PRICE EXTENSION (Quantity times unit price)
		QUANTITY	UNIT OF MEASURE	UNIT PRICE

Wording for "description" is to be provided by the Owner. All Quantities Estimated. The Contractor will be paid based upon actual quantities as verified by the Owner.

Begin @ Sta. 0+00 @ Various Marked Panels

Item	Description	Length	Width	Quantity	Unit
	<p>General Notes:</p> <ol style="list-style-type: none"> 1. Contractor shall field verify all quantities and measurements. 2. Contractor shall be responsible for locating and protecting all existing utilities. 3. Two-way traffic shall be maintained at all times during construction. Contractor shall have flagmen on both ends of work zone. If Police details are used for traffic control this does not take the place of flag men. 4. Construction work shall not begin until signs, barricades, project signs and other traffic devices have been erected and approved. Contractor shall maintain project and construction signs. 5. All existing sewer lines shall be tied-in at no direct pay. 6. Asphalt and concrete driveway tie-ins shall be tied in to existing surface material. 7. At all intersecting asphalt roads, contractor shall mill 1 ½” deep and 6’ into intersecting road for a smooth and clean transition. See Detail attached with Bid Proposal. 8. Any additional work performed by the contractor without prior written approval from St Tammany Parish Department of Engineering, the cost of the work will be borne by the contractor and will not be reimbursed by the Parish. 9. Contractor shall ensure roadway and shoulders drain accordingly without any surface ponding/”bird baths” after rain events. 10. Materials Testing: All required testing and reporting shall be the contractor’s responsibility at no direct pay. Sampling and Testing will be performed in accordance with the St. Tammany Parish Roadway Testing and Inspection Standards for Residential Subdivisions (Attached with Bid Proposal) and LADOTD Standard Specifications for Roads and Bridges, Latest Edition, Section 101 and 106. 11. Roads and surrounding areas shall be dressed after 3 calendar days and no later than 10 calendar days of final asphalt wearing course. Late Fee of \$1.00 per Linear Foot per Calendar Day shall be charged if not completed with the specified time frame. 12. If deep patching is required, the contractor is to compact at a minimum two equal lifts. <p>Project Summary: Contractor shall provide all labor, materials, equipment and supervision necessary to Remove, Replace and/or Repair Concrete Panels and Concrete Rollover Curbs (where applicable)</p> <p>Mobilization: All labor and materials necessary to accomplish preparatory work and operations, including those necessary for movement of personnel, equipment, supplies and incidentals to the project site.</p>				
727-01				1	Lump Sum

All Work Shall Conform to Louisiana Standard Specifications for Roads and Bridges, Latest Edition

Begin @ Sta. 0+00 @ Various Marked Panels

Item	Description	Length	Width	Quantity	Unit
713-01	<p>Temporary Signs and Barricades: All labor, materials, equipment and supervision necessary to furnish, install, maintain and remove temporary construction barricades, precast concrete barriers, lights, signals, pavement markings and signs, including project signs; providing flaggers; and complying with all other requirements regarding the protection of the work, workers and safety of the public. Unless otherwise noted in the plans or special provisions this work also includes traffic control management in compliance with contract documents and the Manual on Uniform Traffic Control Devices (MUTCD), including the installation, inspection, maintenance, and removal of all traffic control devices on the project. This item shall not be construed to relieve the contractor of responsibilities for the safety of the public, for liability in connection therewith, or compliance with State and local laws or ordinances. Signs, barricades, barriers, channelizing devices, pavement markings, etc., shall comply with plan details, the MUTCD and Section 713 of LADOTD Standard Specifications for Roads and Bridges, Latest Edition. Construction work shall not begin until signs, barricades, project signs and other traffic devices have been erected and approved.</p>			1	Lump Sum

Begin @ Sta. 0+00 @ Various Marked Panels

Item	Description	Length	Width	Quantity	Unit
706-03-00500	<p>Remove/Replace/Repair Concrete Panels and Concrete Rollover Curb (where applicable): All labor, materials, equipment and supervision necessary to, in accordance with these specifications, Remove/Replace/Repair Concrete Pavement Detail, Rollover Curb Detail and LA DOTD Standard Specifications for Roads and Bridges, Section 706 and Section 202.03(a), Latest Edition. Contractor shall be responsible for removal of concrete and all base materials to a depth of 8" below the bottom grade of the new 8" thick concrete panel. Replacement base material shall be River Sand or Pumped Sand. Base repair and/or patch is not limited to a square yardage quantity, but may include the entire panel if directed by Department of Public Works inspection staff. This item is at no direct pay. Prior to contractor pouring replacement concrete panel and rollover curb, base material shall be examined by project inspector. Contractor shall inspect the project site and bid accordingly. Panels identified for removal and replacement next to and/or adjacent to new panels shall be saw-cut along the adjoining edge. Any damage caused by contractor operations shall be repaired immediately at no direct pay.</p> <p>Replacement panels shall be Fiber reinforced, 4000psi, 8" thick concrete, with #9 x 18" smooth dowel bars into existing concrete pavement @ 18" on-center for butt/construction joints. Use #4 deformed bar for longitudinal joints 2' on center. When curbing is not poured monolithic, curb pins shall be added @ 18" on center. See Concrete Panel Replacement Detail and Rollover Curb Detail And fiber specification sheet.</p> <p>Joints shall be replaced in-kind, to include but not limited to expansion joints, control joints, etc., and sealed with approved joint sealing material.</p> <p>Broken concrete shall be removed and hauled to an area identified by project inspector at no direct pay.</p>			575	Square yard

Begin @ Sta. 0+00 @ Various Marked Panels

Item	Description	Length	Width	Quantity	Unit
	<p>FIBER-REINFORCED PORTLAND CEMENT CONCRETE ROADWAYS This item covers the furnishing of all materials and installation of PCC roadway pavements for thickness as shown.</p> <p><u>Mix for 1 C.Y. of Fiber-Reinforced Concrete – Sidewalks & Driveways</u></p> <ul style="list-style-type: none"> 28-day strength 4000 psi Cement (ASTM C-150, Type I/II) 4.64 sacks (436 lbs.) Fly Ash (ASTM C-618) 1.16 sacks(109 lbs.) Gravel (ASTM C-33, Grade A) 1775 lbs. Sand (ASTM C-33) 1226 lbs. Water (potable) 30 gallons (250 lbs.) Type A Water Reducer (ASTM C-494) 16.35 lbs. Air entrainment 5% by volume, use per manufacturers specifications Fiber reinforcement 1.5 lbs/ CY microfibers, as specified below <p>Fiber reinforcement for all concrete pavements shall be Matrix Monofilament Microfiber as manufactured by FRC Industries or approved equal, applied throughout the concrete mixture. Alternate products must be preapproved by the Parish Engineer in writing. Cellulose (treated or untreated), AR glass, nylon, and polyester fibers are specifically prohibited from use. Fibrillated and self-fibrillating fibers are also specifically prohibited.</p> <p>Fiber reinforcement shall be applied at the plant. The bags must be broken before mixing. Bag size shall be one (1) pound.</p> <p>Damaged, missing, and/ or new dowel bars (longitudinal/ transverse) and Starlugs shall be replaced, #9 x 18" painted smooth dowel bars on 18" centers shall be used unless directed otherwise by the Parish Engineer. The bars shall be drilled and doweled into the existing pavement by drilling 1½" holes to a depth of 9" and filling with an approved epoxy grout before insertion of the dowel bars. Any deformed bars for longitudinal joints or welded wire fabric will be incidental to the bid unit prices under this item. All costs incurred for this task will be incidental to bid unit prices under concrete paving. Bid prices shall also include adequate curing of the concrete placed and the proper sealing of contraction and expansion joints.</p> <p>The Contractor is advised that the work along roadways will necessarily be done with a split-paving method. It will be important to have at least one side of the roadway open to traffic when workers are not present.</p>				

All Work Shall Conform to Louisiana Standard Specifications for Roads and Bridges, Latest Edition

Begin @ Sta. 0+00 @ Various Marked Panels

Item	Description	Length	Width	Quantity	Unit
------	-------------	--------	-------	----------	------

FIBER-REINFORCED PORTLAND CEMENT CONCRETE ROADWAYS

This item covers the furnishing of all materials and installation of PCC roadway pavements for thickness as shown.

Mix for 1 C.Y.

- 28-day strength 4000 psi
- Cement (ASTM C-150, Type I/II) 4.64 sacks (436 lbs.)
- Fly Ash (ASTM C-618) 1.16 sacks (109 lbs.)
- Gravel (ASTM C-33, Grade A) 1775 lbs.
- Sand (ASTM C-33) 1226 lbs.
- Water (potable) 30 gallons (250 lbs.)
- Type A Water Reducer (ASTM C-494) 16.35 lbs.
- Air entrainment 5% by volume, use per manufacturers specifications
- Fiber reinforcement 1.5 lbs/ CY microfibers, as specified below

Fiber reinforcement for all concrete pavements shall be Matrix Monofilament Microfiber as manufactured by FRC Industries or approved equal, applied throughout the concrete mixture. Alternate products must be preapproved by the Parish Engineer in writing. Cellulose (treated or untreated), AR glass, nylon, and polyester fibers are specifically prohibited from use. Fibrillated and self-fibrillating fibers are also specifically prohibited.

Fiber reinforcement shall be applied **at the plant**. The bags must be broken before mixing. Bag size shall be one (1) pound.

Damaged, missing, and/ or new dowel bars (longitudinal/ transverse) and Starlugs shall be replaced, #9 x 18" painted smooth dowel bars on 18" centers shall be used unless directed otherwise by the Parish Engineer. The bars shall be drilled and doweled into the existing pavement by drilling 1½" holes to a depth of 9" and filling with an approved epoxy grout before insertion of the dowel bars. Any deformed bars for longitudinal joints or welded wire fabric will be incidental to the bid unit prices under this item. All costs incurred for this task will be incidental to bid unit prices under concrete paving. Bid prices shall also include adequate curing of the concrete placed and the proper sealing of contraction and expansion joints.

The Contractor is advised that the work along roadways will necessarily be done with a split-paving method. It will be important to have at least one side of the roadway open to traffic when workers are not present. Bid prices should include all costs for labor, equipment, and materials necessary to provide finished Portland Cement Concrete paving, in place, as described under this item of the proposal. All required jointing materials should be included in price bid under each item. Method of jointing shall be the same as the existing joints in the area of work.

Bid prices under this item shall also include cost of providing engineering/ surveying for alignment, grade, profile, survey stakes, and topography when necessary and as required to improve the roadway alignment, curb and gutter layout, drain line installation, etc. This includes new road, extension of existing road, and turning lanes, parking lots, bike, and walking trails, etc. All layouts shall be the responsibility of the contractor. The Contractor shall be responsible for disposal of all construction materials.

Concrete pavement shall be cured seven (7) days unless otherwise approved by the Parish Engineer. Contractor may use "high early" strength concrete (3-day curing period) at his discretion, with the approval of the Construction Manager at no additional cost. Contractor shall be responsible for proper oversight and protection of the pavement during the initial curing time until the concrete is sufficiently set to resist marring or vandalism.

Begin @ Sta. 0+00 @ Panels marked in the field

Item	Description	Length	Width	Quantity	Unit
	<p>General Notes:</p> <ol style="list-style-type: none"> 1. Contractor shall field verify all quantities and measurements. 2. Contractor shall be responsible for locating and protecting all existing utilities. 3. Two-way traffic shall be maintained at all times during construction. Contractor shall have flagmen on both ends of work zone. If Police details are used for traffic control this does not take the place of flag men. 4. Construction work shall not begin until signs, barricades, project signs and other traffic devices have been erected and approved. Contractor shall maintain project and construction signs. 5. All existing sewer lines shall be tied-in at no direct pay. 6. Asphalt and concrete driveway tie-ins shall be tied in to existing surface material. 7. At all intersecting asphalt roads, contractor shall mill 1 ½” deep and 6’ into intersecting road for a smooth and clean transition. See Detail attached with Bid Proposal. 8. Any additional work performed by the contractor without prior written approval from St Tammany Parish Department of Engineering, the cost of the work will be borne by the contractor and will not be reimbursed by the Parish. 9. Contractor shall ensure roadway and shoulders drain accordingly without any surface ponding/”bird baths” after rain events. 10. Materials Testing: All required testing and reporting shall be the contractor’s responsibility at no direct pay. Sampling and Testing will be performed in accordance with the St. Tammany Parish Roadway Testing and Inspection Standards for Residential Subdivisions (Attached with Bid Proposal) and LADOTD Standard Specifications for Roads and Bridges, Latest Edition, Section 101 and 106. 11. Roads and surrounding areas shall be dressed after 3 calendar days and no later than 10 calendar days of final asphalt wearing course. Late Fee of \$1.00 per Linear Foot per Calendar Day shall be charged if not completed with the specified time frame. 12. If deep patching is required, the contractor is to compact at a minimum two equal lifts. <p>Project Summary: Contractor shall provide all labor, materials, equipment and supervision necessary to Remove, Replace and/or Repair Concrete Panels and Concrete Rollover Curbs.</p> <p>Mobilization: All labor and materials necessary to accomplish preparatory work and operations, including those necessary for movement of personnel, equipment, supplies and incidentals to the project site.</p>				
727-01				1	Lump Sum

All Work Shall Conform to Louisiana Standard Specifications for Roads and Bridges, Latest Edition

Begin @ Sta. 0+00 @ Panels marked in the field

Item	Description	Length	Width	Quantity	Unit
713-01	<p>Temporary Signs and Barricades: All labor, materials, equipment and supervision necessary to furnish, install, maintain and remove temporary construction barricades, precast concrete barriers, lights, signals, pavement markings and signs, including project signs; providing flaggers; and complying with all other requirements regarding the protection of the work, workers and safety of the public. Unless otherwise noted in the plans or special provisions this work also includes traffic control management in compliance with contract documents and the Manual on Uniform Traffic Control Devices (MUTCD), including the installation, inspection, maintenance, and removal of all traffic control devices on the project. This item shall not be construed to relieve the contractor of responsibilities for the safety of the public, for liability in connection therewith, or compliance with State and local laws or ordinances. Signs, barricades, barriers, channelizing devices, pavement markings, etc., shall comply with plan details, the MUTCD and Section 713 of LADOTD Standard Specifications for Roads and Bridges, Latest Edition. Construction work shall not begin until signs, barricades, project signs and other traffic devices have been erected and approved.</p>			1	Lump Sum

All Work Shall Conform to Louisiana Standard Specifications for Roads and Bridges, Latest Edition

Begin @ Sta. 0+00 @ Panels marked in the field

Item	Description	Length	Width	Quantity	Unit
706-03-00500	<p>Remove/Replace/Repair Concrete Panels and Concrete Rollover Curb: All labor, materials, equipment and supervision necessary to, in accordance with these specifications, Remove/Replace/Repair Concrete Pavement Detail, Rollover Curb Detail and LA DOTD Standard Specifications for Roads and Bridges, Section 706 and Section 202.03(a), Latest Edition. Contractor shall be responsible for removal of concrete and all base materials to a depth of 8" below the bottom grade of the new 8" thick concrete panel. Replacement base material shall be River Sand or Pumped Sand. Base repair and/or patch is not limited to a square yardage quantity, but may include the entire panel if directed by Department of Public Works inspection staff. This item is at no direct pay. Prior to contractor pouring replacement concrete panel and rollover curb, base material shall be examined by project inspector. Contractor shall inspect the project site and bid accordingly. Panels identified for removal and replacement next to and/or adjacent to new panels shall be saw-cut along the adjoining edge. Any damage caused by contractor operations shall be repaired immediately at no direct pay.</p> <p>Replacement panels shall be Fiber reinforced, 4000psi, 8" thick concrete, with #9 x 18" smooth dowel bars into existing concrete pavement @ 18" on-center for butt/construction joints. Use #4 deformed bar for longitudinal joints 2' on center. When curbing is not poured monolithic, curb pins shall be added @ 18" on center. See Concrete Panel Replacement Detail and Rollover Curb Detail And fiber specification sheet.</p> <p>Joints shall be replaced in-kind, to include but not limited to expansion joints, control joints, etc., and sealed with approved joint sealing material.</p> <p>Broken concrete shall be removed and hauled to an area identified by project inspector at no direct pay.</p>			200	Square Yard

Begin @ Sta. 0+00 @ Panels marked in the field

Item	Description	Length	Width	Quantity	Unit
	<p>FIBER-REINFORCED PORTLAND CEMENT CONCRETE ROADWAYS This item covers the furnishing of all materials and installation of PCC roadway pavements for thickness as shown.</p> <p><u>Mix for 1 C.Y. of Fiber-Reinforced Concrete – Sidewalks & Driveways</u></p> <ul style="list-style-type: none"> 28-day strength 4000 psi Cement (ASTM C-150, Type I/II) 4.64 sacks (436 lbs.) Fly Ash (ASTM C-618) 1.16 sacks(109 lbs.) Gravel (ASTM C-33, Grade A) 1775 lbs. Sand (ASTM C-33) 1226 lbs. Water (potable) 30 gallons (250 lbs.) Type A Water Reducer (ASTM C-494) 16.35 lbs. Air entrainment 5% by volume, use per manufacturers specifications Fiber reinforcement 1.5 lbs/ CY microfibers, as specified below <p>Fiber reinforcement for all concrete pavements shall be Matrix Monofilament Microfiber as manufactured by FRC Industries or approved equal, applied throughout the concrete mixture. Alternate products must be preapproved by the Parish Engineer in writing. Cellulose (treated or untreated), AR glass, nylon, and polyester fibers are specifically prohibited from use. Fibrillated and self-fibrillating fibers are also specifically prohibited.</p> <p>Fiber reinforcement shall be applied at the plant. The bags must be broken before mixing. Bag size shall be one (1) pound.</p> <p>Damaged, missing, and/ or new dowel bars (longitudinal/ transverse) and Starlugs shall be replaced, #9 x 18" painted smooth dowel bars on 18" centers shall be used unless directed otherwise by the Parish Engineer. The bars shall be drilled and doweled into the existing pavement by drilling 1½" holes to a depth of 9" and filling with an approved epoxy grout before insertion of the dowel bars. Any deformed bars for longitudinal joints or welded wire fabric will be incidental to the bid unit prices under this item. All costs incurred for this task will be incidental to bid unit prices under concrete paving. Bid prices shall also include adequate curing of the concrete placed and the proper sealing of contraction and expansion joints.</p> <p>The Contractor is advised that the work along roadways will necessarily be done with a split-paving method. It will be important to have at least one side of the roadway open to traffic when workers are not present.</p>				

All Work Shall Conform to Louisiana Standard Specifications for Roads and Bridges, Latest Edition

Begin @ Sta. 0+00 @ Panels marked in the field

Item	Description	Length	Width	Quantity	Unit
------	-------------	--------	-------	----------	------

FIBER-REINFORCED PORTLAND CEMENT CONCRETE ROADWAYS

This item covers the furnishing of all materials and installation of PCC roadway pavements for thickness as shown.

Mix for 1 C.Y. of Fiber-Reinforced Concrete – Sidewalks & Driveways

- 28-day strength 4000 psi
- Cement (ASTM C-150, Type I/II) 4.64 sacks (436 lbs.)
- Fly Ash (ASTM C-618) 1.16 sacks(109 lbs.)
- Gravel (ASTM C-33, Grade A) 1775 lbs.
- Sand (ASTM C-33) 1226 lbs.
- Water (potable) 30 gallons (250 lbs.)
- Type A Water Reducer (ASTM C-494) 16.35 lbs.
- Air entrainment 5% by volume, use per manufacturers specifications
- Fiber reinforcement 1.5 lbs/ CY microfibers, as specified below

Fiber reinforcement for all concrete pavements shall be Matrix Monofilament Microfiber as manufactured by FRC Industries or approved equal, applied throughout the concrete mixture. Alternate products must be preapproved by the Parish Engineer in writing. Cellulose (treated or untreated), AR glass, nylon, and polyester fibers are specifically prohibited from use. Fibrillated and self-fibrillating fibers are also specifically prohibited.

Fiber reinforcement shall be applied **at the plant**. The bags must be broken before mixing. Bag size shall be one (1) pound.

Damaged, missing, and/ or new dowel bars (longitudinal/ transverse) and Starlugs shall be replaced, #9 x 18" painted smooth dowel bars on 18" centers shall be used unless directed otherwise by the Parish Engineer. The bars shall be drilled and doweled into the existing pavement by drilling 1½" holes to a depth of 9" and filling with an approved epoxy grout before insertion of the dowel bars. Any deformed bars for longitudinal joints or welded wire fabric will be incidental to the bid unit prices under this item. All costs incurred for this task will be incidental to bid unit prices under concrete paving. Bid prices shall also include adequate curing of the concrete placed and the proper sealing of contraction and expansion joints.

The Contractor is advised that the work along roadways will necessarily be done with a split-paving method. It will be important to have at least one side of the roadway open to traffic when workers are not present. Bid prices should include all costs for labor, equipment, and materials necessary to provide finished Portland Cement Concrete paving, in place, as described under this item of the proposal. All required jointing materials should be included in price bid under each item. Method of jointing shall be the same as the existing joints in the area of work.

Bid prices under this item shall also include cost of providing engineering/ surveying for alignment, grade, profile, survey stakes, and topography when necessary and as required to improve the roadway alignment, curb and gutter layout, drain line installation, etc. This includes new road, extension of existing road, and turning lanes, parking lots, bike, and walking trails, etc. All layouts shall be the responsibility of the contractor. The Contractor shall be responsible for disposal of all construction materials.

Concrete pavement shall be cured seven (7) days unless otherwise approved by the Parish Engineer. Contractor may use "high early" strength concrete (3-day curing period) at his discretion, with the approval of the Construction Manager at no additional cost. Contractor shall be responsible for proper oversight and protection of the pavement during the initial curing time until the concrete is sufficiently set to resist marring or vandalism.

All Work Shall Conform to Louisiana Standard Specifications for Roads and Bridges, Latest Edition