



## ST. TAMMANY PARISH

PATRICIA P. BRISTER  
PARISH PRESIDENT

**May 17, 2018**

Please find the following addendum to the below mentioned BID.

**Addendum No.:** 1  
**Bid#:** 314-00-18-04-2  
**Project Name:** Queen Anne Drainage  
**Bid Due Date:** May 22, 2018

### **GENERAL INFORMATION:**

---

1. Please see the attached Mandatory Pre-Bid Sign-In Sheet. (Attached)
2. Please remove "Unit Price Form" from Section 04 and replace with "Unit Price Form Revised". (Attached)
3. Please remove "Summary of Estimated Quantities" from Section 11 and replace with "Summary of Estimated Quantities Revised". (Attached)
4. Camp Salmen is open Friday through Sunday. Contractor should expect a high volume of pedestrians those days and secure project site.

### **QUESTIONS & ANSWERS:**

---

**Question #1:** Will tail water conditions from Bayou Liberty affect ability to cross the W12 to reach project site?

**Answer #1:** No, the temporary crossing will make the project site accessible through most conditions, with the exception of a tropical event. Should a tropical threat occur, the site will be evaluated and a decision made by the Parish regarding the crossing.

**Question #2:** Will sod be required at the pipe joint repair locations?

**Answer #2:** Yes, soils disturbed by pipe joint repair activities will require sodding. A pay item for sod has been added.

**Question #3:** How is debris disposed of?

**Answer #3:** All debris (including, but not limited to trees, shrubs, excavated material, etc.) shall become the property of the contractor and shall be hauled off-site and disposed of in a lawful manner. Costs associated with disposal shall be borne by the contractor.



## ST. TAMMANY PARISH

PATRICIA P. BRISTER  
PARISH PRESIDENT

Question #4: Where is the temporary crossing located?

**Answer #4:** Location of crossing is noted on Sheet 4 of the plan set.

Question #5: Are mats acceptable for crossing the W12 in lieu of temporary crossing?

**Answer #5:** Yes, however, no extra time will be given should canal become impassable due to tail water conditions or rain events.

### **ATTACHMENTS:**

---

1. Mandatory Pre-Bid Sign-In Sheet.pdf
2. Unit Price Form Revised.pdf
3. Summary of Estimated Quantities Revised.pdf

**<< End of Addendum #1 >>**

**Mandatory Pre-Bid Sign-In Sheet**  
**Queen Anne Drainage**

**Location**

On-Site at Queen Anne Drive and Charles Drive Sidelall,  
LA 70460

	Name	Company	Email	Phone	Time In	Time Out
1	Desiree Harman	Magee Excavation	skip@mageexcavation.com	9853738297	9:45	10:35
2	Eric Penton	Day Star Builders Inc.	ep@daystarbuilders.com	985-710-3777	9:50	10:35
3	Gina Duplessis	Gulf States Contractors	gduplessis@gulfstatescontractors.com	985-259-4460	9:45	10:35
4	Robert Foster	ROBERT FOSTER CONSTRUCTION	ROBERT FOSTER CONSTRUCTION.COM	(985)949-6978	9:45	10:35
5	Kevin McDonald	McDonald Const. Inc.	Ksmcdona@bellsouth.net	985-960-0006	9:50	10:35
6	Brian Mathe	Boh Bros.	bmathe@bohbro.com	504-821-2400	9:50	10:35
7	Thomas Bellan	Command Const.	thomasc@commandindustries.com	5048878795	9:50	10:35
8	Aaron LeBourgeois	Bucktown Contractors	bucktowninc@aol.com	504-382-3094	9:50	10:35
9	Jason Clement	LSI	jasonc@lagrecahd.com	985-637-0004	9:50	10:35
10	Mike Warner	Warner Trenching	mike.warner.trenching@gmail.com	985-705-5943	9:55	10:35
11						
12						
13						

# LOUISIANA UNIFORM PUBLIC WORK BID FORM UNIT PRICE FORM - REVISED

TO:

St. Tammany Parish Government  
21454 Koop Drive, Suite 2F  
Mandeville, LA. 70471

BID FOR:

Queen Anne Drainage  
Bid # 314-00-18-04-2

(OWNER TO PROVIDE NAME AND ADDRESS OF OWNER)

(OWNER TO PROVIDE PROJECT NAME & OTHER IDENTIFYING INFO)

**UNIT PRICES: This form shall be used for any & all work required by the Bidding Documents & described as unit prices. Amounts shall be stated in figures & only in figures.**

REF NO.:	Description:	<input checked="" type="checkbox"/> BASE BID    OR <input type="checkbox"/> ALT #		Clearing and Grubbing		UNIT PRICE EXTENSION (Quantity times unit price)
		QUANTITY	UNIT OF MEASURE	UNIT PRICE	UNIT PRICE EXTENSION (Quantity times unit price)	
202-01-00100		1	LUMP			
	Description:	<input checked="" type="checkbox"/> BASE BID    OR <input type="checkbox"/> ALT #		Removal of Walks and Drives		
202-02-06100		5	SQYD			
	Description:	<input checked="" type="checkbox"/> BASE BID    OR <input type="checkbox"/> ALT #		General Excavation (Net Section)		
203-01-00100		201	CUYD			
	Description:	<input checked="" type="checkbox"/> BASE BID    OR <input type="checkbox"/> ALT #		Embankment (Net Section)		
203-03-00100		405	CUYD			

**Wording for "description" is to be provided by the Owner. All Quantities Estimated. The Contractor will be paid based upon actual quantities as verified by the Owner.**

**UNIT PRICES:** This form shall be used for any & all work required by the Bidding Documents & described as unit prices. Amounts shall be stated in figures & only in figures.

REF NO.:	Description:	<input checked="" type="checkbox"/> BASE BID   OR <input type="checkbox"/> ALT #		Borrow (Net Section)		UNIT PRICE EXTENSION (Quantity times unit price)	
		QUANTITY	UNIT OF MEASURE	UNIT PRICE	UNIT PRICE EXTENSION (Quantity times unit price)		
203-07-00100		130	CUYD				
	<b>Description:</b>	<input checked="" type="checkbox"/> BASE BID   OR <input type="checkbox"/> ALT #	Storm Drain Pipe (54" RCP)				
701-03-01120		120	LNFT				
	<b>Description:</b>	<input checked="" type="checkbox"/> BASE BID   OR <input type="checkbox"/> ALT #	Catch Basins (CB-02)				
702-03-00200		1	EACH				
	<b>Description:</b>	<input checked="" type="checkbox"/> BASE BID   OR <input type="checkbox"/> ALT #	Riprap (55 lb, 18" thick)				
711-01-02040		100	SQYD				
	<b>Description:</b>	<input checked="" type="checkbox"/> BASE BID   OR <input type="checkbox"/> ALT #	Temporary Signs and Barricades				
713-01-00100		1	LUMP				
	<b>Description:</b>	<input checked="" type="checkbox"/> BASE BID   OR <input type="checkbox"/> ALT #	Slab Sodding (Common Bermuda)				
714-01-00500		100	SQYD				

**Wordings for "description" is to be provided by the Owner. All Quantities Estimated. The Contractor will be paid based upon actual quantities as verified by the Owner.**

**UNIT PRICES:** This form shall be used for any & all work required by the Bidding Documents & described as unit prices. Amounts shall be stated in figures & only in figures.

REF NO.:	Description:	<input checked="" type="checkbox"/> BASE BID   OR <input type="checkbox"/> ALT #		Bedding Material (Net Section)		UNIT PRICE EXTENSION (Quantity times unit price)
		QUANTITY	UNIT OF MEASURE	UNIT PRICE	UNIT PRICE EXTENSION (Quantity times unit price)	
726-01-00100		53	CUYD			
	Description:	<input checked="" type="checkbox"/> BASE BID   OR <input type="checkbox"/> ALT #		Mobilization		
727-01-00100		1	LUMP			
	Description:	<input checked="" type="checkbox"/> BASE BID   OR <input type="checkbox"/> ALT #		Hydro-Seeding		
739-01-00100		0.5	ACRE			
	Description:	<input checked="" type="checkbox"/> BASE BID   OR <input type="checkbox"/> ALT #		Construction Layout		
740-01-00100		1	LUMP			
	Description:	<input checked="" type="checkbox"/> BASE BID   OR <input type="checkbox"/> ALT #		Drainage Structure (Catch Basin Top and Frame)		
NS-MS-00120		1	EACH			
	Description:	<input checked="" type="checkbox"/> BASE BID   OR <input type="checkbox"/> ALT #		Pipe Joint Repair		
NS-0001		10	EACH			
	Description:	<input checked="" type="checkbox"/> BASE BID   OR <input type="checkbox"/> ALT #		Pipe Joint Repair		

**Wordings for "description" is to be provided by the Owner. All Quantities Estimated. The Contractor will be paid based upon actual quantities as verified by the Owner.**

**UNIT PRICES:** This form shall be used for any & all work required by the Bidding Documents & described as unit prices. Amounts shall be stated in figures & only in figures.

Description:		<input checked="" type="checkbox"/> BASE BID	OR	<input type="checkbox"/> ALT #	Flap Gate (54") (Stainless Steel)	
REF NO.:	QUANTITY	UNIT OF MEASURE	UNIT PRICE	UNIT PRICE EXTENSION (Quantity times unit price)		
NS-0002	1	EACH				
Description:		<input checked="" type="checkbox"/> BASE BID	OR	<input type="checkbox"/> ALT #	Temporary Channel Crossing	
REF NO.:	QUANTITY	UNIT OF MEASURE	UNIT PRICE	UNIT PRICE EXTENSION (Quantity times unit price)		
NS-0003	1	EACH				
Description:		<input type="checkbox"/> BASE BID	OR	<input type="checkbox"/> ALT #		
REF NO.:	QUANTITY	UNIT OF MEASURE	UNIT PRICE	UNIT PRICE EXTENSION (Quantity times unit price)		
Description:		<input type="checkbox"/> BASE BID	OR	<input type="checkbox"/> ALT #		
REF NO.:	QUANTITY	UNIT OF MEASURE	UNIT PRICE	UNIT PRICE EXTENSION (Quantity times unit price)		
Description:		<input type="checkbox"/> BASE BID	OR	<input type="checkbox"/> ALT #		
REF NO.:	QUANTITY	UNIT OF MEASURE	UNIT PRICE	UNIT PRICE EXTENSION (Quantity times unit price)		
Description:		<input type="checkbox"/> BASE BID	OR	<input type="checkbox"/> ALT #		
REF NO.:	QUANTITY	UNIT OF MEASURE	UNIT PRICE	UNIT PRICE EXTENSION (Quantity times unit price)		

**Wordings for "description" is to be provided by the Owner. All Quantities Estimated. The Contractor will be paid based upon actual quantities as verified by the Owner.**

REVISED  
SUMMARY OF ESTIMATED QUANTITIES

<u>Item No.</u>	<u>Description</u>	<u>Quantity</u>	<u>Unit</u>
201-01-00100	Clearing and Grubbing	1	LUMP
202-02-06100	Removal of Concrete Walks and Drives	5	SQYD
203-01-00100	General Excavation (Net Section)	201	CUYD
203-03-00100	Embankment (Net Section)	405	CUYD
203-07-00100	Borrow (Net Section)	130	CUYD
701-03-01120	Storm Drain Pipe (54" RCP)	120	LNFT
702-03-00200	Catch Basins (CB-02)	1	EACH
711-01-02040	Riprap (55 lb, 18" Thick)	100	SQYD
713-01-00100	Temporary Signs and Barricades	1	LUMP
714-01-00500	Slab Sodding (Common Bermuda)	100	SQYD
726-01-00100	Bedding Material (Net Section)	53	CUYD
727-01-00100	Mobilization	1	LUMP
739-01-00100	Hydro-Seeding	0.5	ACRE
740-01-00100	Construction Layout	1	LUMP
NS-MS-00120	Drainage Structure (Catch Basin Top and Frame)	1	EACH
NS-0001	Pipe Joint Repair	10	EACH
NS-0002	Flap Gate (54")(Stainless Steel)	1	EACH
NS-0003	Temporary Channel Crossing	1	EACH

Rev. No	Date	Description

