



## ST. TAMMANY PARISH

PATRICIA P. BRISTER  
PARISH PRESIDENT

**August 23, 2018**

Please find the following addendum to the below mentioned QUOTE.

**Addendum No.:** 1

**Quote#:** 300-00-18-19-1

**Project Name:** FEMA Disaster 4263 PW 439 Tallow Creek Bridge

**Quote Due Date:** Wednesday, August 29, 2018

### QUESTIONS & ANSWERS:

---

**Question #1:** Is there an additional access road for the residents while work is ongoing or does the work has to be divided by lane (ingress/egress)?

**Answer #1:** There is no other point of ingress/egress for residents. Split slab construction will be required divided by lane width appropriate signage and barricades.

**Question #2:** Is the work to be performed at night if only one access road?

**Answer #2:** Work hours are not limited to night only.

**Question #3:** Is there an established or preferred method for the Toe Treatment or Protection Against Scour? With the existing slope the rock will slide into the stream.

**Answer #3:** A trench two times the thickness of the riprap with the geotextile fabric tucked into the riprap is the preferred toe treatment to protect against scour.

**<< End of Addendum #1 >>**