

April 17, 2019

Please find the following addendum to the below mentioned BID.

Addendum No.: 1

Bid#: 19-09-2

Project Name: Parishwide Drainage Repairs

Bid Due Date: Thursday, April 23, 2019

GENERAL INFORMATION:

- 1. Please remove "Nottingham Specifications" and replace with "Nottingham Specifications Revised". (Attached)
- 2. Please remove "Unit Price Sheet" and replace with "Unit Price Sheet Revised". (Attached)

QUESTIONS & ANSWERS:

- Question 1: Upon a Site visit to several locations of Repairs the depth of the Pipe to be repaired is 10' deep to invert. Can a Unit Price for Shoring or some type of Safety measures be added?
- Answer 1: Deepest invert is 5'6" from top of casting. No trench box will be required at that depth. If Contractor has to shore up with timber it will be done at no direct pay.
- Question 2: If a Tree, Fence, Mailbox or Utility Service Pole conflicts with practical constructability, how does this get paid?
- Answer 2: If a utility pole or underground utility prevents the use of mechanical equipment those areas are to be hand dug at no direct pay. Item to be added

to the Unit Price Sheet to remove and replace a section of fence, trees, and mailbox.

Question 3: Can work be performed at night in high traffic areas?

Answer 3: Night work is prohibited. Per the general notes, the contractor is required to supply, install and maintain all traffic control devices and provide flagmen Per LA DOTD specifications at no direct pay.

ATTACHMENTS:

- 1. Nottingham Specifications Revised.pdf
- 2. Unit Price Sheet Revised.pdf

End of Addendum #1

Name: Nottingham Ln. (R08V027) Project Number: PW18000206 Date: Revised 4-9-19 Page 1 of 3

Sink Hole Repairs. (East of Brookter St.)

Item	Description	Length	Width	Quantity	Unit
	 General Notes: Contractor shall field verify all quantities and measurements. Contractor shall be responsible for locating and protecting all existing utilities. Two-way traffic shall be maintained at all times during construction. Prior to beginning work, contractor will provide temporary signs and barricades at 0 direct pay: furnish, install, maintain and remove temporary signs, construction signs and / or barricades; and provide flagmen to comply with all other requirements regarding the projection of the work, workers and safety of the public. Work shall be done in accordance with LA DOTD Standard Specifications for Roads and Bridges, Sec. 713. Driveway aprons shall be tied-in to existing hard surfaced drives or extend two (2) feet behind the culvert, whichever is greater. For clarification purposes, tie-in new asphalt to existing asphalt/concrete aprons at no direct pay. All turning radii shall be a minimum of thirty-five (35) feet. All existing sewer lines shall be tied-in at no direct pay. For clarification purposes, tie-in new asphalt to existing asphalt aprons at no direct pay on existing gravel roads. Any <u>additional work</u> performed by the contractor <u>without prior written approval</u> from the St Tammany Parish Department of Engineering, the cost of the work will be borne by the contractor and will not be reimbursed by the Parish. 				
	Project Summary: All labor and materials necessary to clean, repair and reseal (1) catch basin, replace (1) concrete and clean, repair and re-seal culverts from the inside				
727-01	Mobilization : All labor and materials necessary to accomplish preparatory work and operations, including those necessary for movement of personnel, equipment, supplies and incidentals to the project site. Mobilization costs shall follow rules called out in the LA DOTD Standard Specifications for Roads and Bridges, Sec. 727.			1	Lump Sum

Name: Nottingham Ln. (R08V027) Project Number: PW18000206 Date: Revised 4-9-19 Page 2 of 3

Sink Hole Repairs.

Item	Description	Length	Width	Quantity	Unit
706- 02- 00200	6" Concrete Drive: All labor and materials necessary to remove and replace broken area of concrete drive. Drive is to be 6" thick and constructed of 4000 psi class B concrete with fiber mesh. All work shall be done in accordance with the LA DOTD Standard Specifications for Roads and Bridges, Sec. 706, 2016 Edition. Work shall include all saw cuts necessary to remove broken section of drive. All debris shall be removed at no direct pay.	14'	7'	11	Square Yards
S-001	Clean, Repair and Reseal Catch Basin: All labor and materials necessary to power wash, repair all cracks and reseal existing catch basin. Work shall include sealing around new pipe where it enters box. Contractor shall use Dayton Superior Re-Crete 20 minute grout or approved equal to re seal box. All debris is to be removed at no direct pay.			2	Each
S-003	Clean, Repair and Re-seal interior Culvert Joints: All labor and materials necessary to go inside the pipe and clean, repair and re-seal all culvert joints. All joints are to be resealed with Dayton Superior Re-Crete 20 minute grout or approved equal. All debris shall be removed at no direct pay			113	Each
705- 06- 00100	Remove and Reinstall Fence: all labor and materials to remove and reinstall both a section of chain link fence and wood fence. Work shall be done per LA DOTD Standard Specifications for Roads and Bridges, Sec.705, 2016 Edition. All debris shall be removed at no direct pay.			30	Linear foot
719- 01- 01000	Remove and Replant Tree. All labor and materials to remove and replant tree as necessary to expose pipe joint. Contractor shall place tree in a protected locations and water as needed until time to replace. All work shall be done in accordance with LA DOTD Standard Specifications for Roads and Bridges, Sec.719, 2016 edition. All debris shall be removed at no direct pay.			3	Each
735- 01- 00100	Remove and Reinstall Mailbox: All labor and materials necessary to remove and reinstall mailbox. Contractor shall replace or repair mailbox if it is damaged during construction. All work shall be done in accordance with LA DOTD Standard Specifications for Roads and Bridges, Sec. 735, 2016 Edition. All debris shall be removed at no direct pay.			1	Each

Name: Nottingham Ln. (R08V027) Project Number: PW18000206 Date: Revised 4-9-19 Page 3 of 3

Sink Hole Repairs.

Iten	Description	Length	Width	Quantity	Unit
203- 03- 0010	Embankment: All labor and materials necessary to provide, install and compact embankment in the sink hole areas located along the house and under the fence. All work shall be done in accordance with LA DOTD Standard Specifications for Roads and Bridges, Sec. 203, 2016 edition. All debris shall be removed at no direct pay.			3	Cubic Yards

LOUISIANA UNIFORM PUBLIC WORK BID FORM UNIT PRICE FORM

<u>TO:</u>	BID FOR:
St. Tammany Parish Government	Parishwide Sinkhole Repairs
21454 Koop Drive, Suite 2F	Bid #19-09-2
Mandeville, LA. 70471	REVISED
(OWNER TO PROVIDE NAME AND ADDRESS OF OWNER)	(OWNER TO PROVIDE PROJECT NAME & OTHER IDENTIFYING INFO)

UNIT PRICES: This form shall be used for any & all work required by the Bidding Documents & described as unit prices. Amounts shall be stated in figures & only in figures.

Description:	■ BASE BID OR	□ ALT#	Mobilization	
REF NO.:	QUANTITY	UNIT OF MEASURE	UNIT PRICE	UNIT PRICE EXTENSION (Quantity times unit price)
727-01	1	LS		
Description:	■ BASE BID OR	□ ALT #	6" Concrete Drive	
REF NO.:	QUANTITY	UNIT OF MEASURE	UNIT PRICE	UNIT PRICE EXTENSION (Quantity times unit price)
706-02-00200	92	SY		
Description:	■ BASE BID OR	□ ALT #	6" Concrete Drain Apron	
REF NO.:	QUANTITY	UNIT OF MEASURE	UNIT PRICE	UNIT PRICE EXTENSION (Quantity times unit price)
706-03-00300	27	SY		
Description:	■ BASE BID OR	□ ALT #	4" Concrete Sidewalk	
REF NO.:	QUANTITY	UNIT OF MEASURE	UNIT PRICE	UNIT PRICE EXTENSION (Quantity times unit price)
706-01-00100	65	SY		

Wording for "description" is to be provided by the Owner. All Quantities Estimated. The Contractor will be paid based upon actual quantities as verified by the Owner.

Version 2017 Q2

UNIT PRICES: This form shall be used for any & all work required by the Bidding Documents & described as unit prices. Amounts shall be stated in figures & only in figures.

Description	: ☑ BASE BID OR	□ ALT#	Clean, Repair and Reseal Catch Basin		
REF NO.:	QUANTITY	UNIT OF MEASURE	UNIT PRICE	UNIT PRICE EXTENSION (Quantity times unit price)	
S-001	32	EA			
Description	: ☑ BASE BID OR	□ ALT #	Reseal and Wrap Culvert Jo	ints with Fabric	
REF NO.:	QUANTITY	UNIT OF MEASURE	UNIT PRICE	UNIT PRICE EXTENSION (Quantity times unit price)	
S-002	150	EA			
Description	: ☑ BASE BID OR	□ ALT #	Clean, Repair and Reseal In	terior Culvert Joint	
REF NO.:	QUANTITY	UNIT OF MEASURE	UNIT PRICE	UNIT PRICE EXTENSION (Quantity times unit price)	
S-003	322	EA			
Description	BASE BID OR	□ ALT #	Clean, Repair and Reseal Ma	anhole	
REF NO.:	QUANTITY	UNIT OF MEASURE	UNIT PRICE	UNIT PRICE EXTENSION (Quantity times unit price)	
S-004	1	EA			
Description	BASE BID OR	□ ALT #	Remove and Reinstall Catch	Basin Lid	
REF NO.:	QUANTITY	UNIT OF MEASURE	UNIT PRICE	UNIT PRICE EXTENSION (Quantity times unit price)	
S-005	7	EA			
Description	BASE BID OR	□ ALT #	Traffic Rated Catch Basin Li	d	
REF NO.:	QUANTITY	UNIT OF MEASURE	UNIT PRICE	UNIT PRICE EXTENSION (Quantity times unit price)	
S-006 Version 2017 Q2	2	EA			

Wording for "description" is to be provided by the Owner. All Quantities Estimated. The Contractor will be paid based upon actual quantities as verified by the Owner.

UNIT PRICES: This form shall be used for any & all work required by the Bidding Documents & described as unit prices. Amounts shall be stated in figures & only in figures.

Description:	■ BASE BID OR	□ ALT #	Sod	
REF NO.:	QUANTITY	UNIT OF MEASURE	UNIT PRICE	UNIT PRICE EXTENSION (Quantity times unit price)
714-01-00100	1	LS		
Description:	■ BASE BID OR	□ ALT #	CB-07 Catch Basin	
REF NO.:	QUANTITY	UNIT OF MEASURE	UNIT PRICE	UNIT PRICE EXTENSION (Quantity times unit price)
703-03-00600	1	EA		
Description:	☑ BASE BID OR	□ ALT #	Remove and Reinstall Fence	
REF NO.:	QUANTITY	UNIT OF MEASURE	UNIT PRICE	UNIT PRICE EXTENSION (Quantity times unit price)
705-06-00100	30	LF		
Description:	☑ BASE BID OR	□ ALT #	Remoe and Replant Tree	
REF NO.:	QUANTITY	UNIT OF MEASURE	UNIT PRICE	UNIT PRICE EXTENSION (Quantity times unit price)
719-06-00100	3	Each		
Description:	☑ BASE BID OR	□ ALT #	Remove and Reinstall Mailbo	x
REF NO.:	QUANTITY	UNIT OF MEASURE	UNIT PRICE	UNIT PRICE EXTENSION (Quantity times unit price)
735-01-00100	1	Each		
Description:	■ BASE BID OR	□ ALT #	Embankment	
REF NO.:	QUANTITY	UNIT OF MEASURE	UNIT PRICE	UNIT PRICE EXTENSION (Quantity times unit price)
203-03-00100 Version 2017 Q2 Wording for "description" is to be provided by the C	3	Cubic Yards		

Wording for "description" is to be provided by the Owner. All Quantities Estimated. The Contractor will be paid based upon actual quantities as verified by the Owner.